



1765 Restoration Road
Rochester MN 55902
507-282-8206

Pool

The following items are conditions for permit issuance and strict compliance is mandatory.

1. Install pool per manufacturer's specifications. Pool installation manual shall be on site at final inspection.
2. Post the attached Inspection Record Card on the jobsite. MSBC1300.0210 subp 3
3. Gas lines shall be properly tested and witnessed by the building inspector.
 - Equipment that is not to be included in the test shall be either disconnected from the piping or isolated by blanks, blind flanges, or caps. Flanged joints at which blinds are inserted to blank off other equipment during the test shall not be required to be tested. IFGC 406.3.2
 - Where the piping system is connected to equipment or components designed for operating pressures of less than the test pressure, such equipment or equipment components shall be isolated from the piping system by disconnecting them and capping the outlet(s). IFGC 406.3.3
 - The test pressure to be used shall be no less than one and one-half times the proposed maximum working pressure, but not less than 25 psig (172 kPa gauge), irrespective of design pressure. IFGC 406.4.1
 - Test duration shall be not less than one-half hour. IFGC 406.4.2
4.
 - a. The term "complete" shall include all work proposed in the approved permit. All building permits issued shall complete construction of the project within one hundred and eighty (180) days after the permit is issued, without additional approval. If at the time of application, the project is anticipated to not be completed within one hundred eighty (180) days, the applicant shall provide the project's anticipated timeline. CMS may adjust for reasonableness and approve project timelines as part of the permit review process up to five hundred and forty (540) days. Projects anticipated to exceed five hundred and forty (540) days shall seek approval from the jurisdiction's applicable governing body.
 - b. A permit holder may request extensions in increments of one hundred and eighty (180) days. CMS may approve up to two extensions if CMS judges steady and continuous progress is being made. Permit holders requesting more than two extensions shall make an application for a new permit. The new permit application shall state the reason and demonstrate that circumstances were beyond the control of the permit holder.
5. This installation must comply with all portions of the Minnesota State Building Code whether noted on this plan or omitted. Failure to note any detail(s) on the plan does not remove the builder from the responsibility of complying with the Building Code. Plan review was done in accordance with the current Minnesota Building Code. Plan review does not waive any additional code compliance issues found on site. MSBC1300