



Sump Pump

The following items are conditions for permit issuance and strict compliance is mandatory.

The following items are conditions for permit issuance and strict compliance is mandatory.

1. Construction documents and a signed copy of the plan shall be kept at the site of the work, and open to inspection by the building inspector. MSBC1300.0130 subp 6
2. The exterior wall envelope shall be designed and constructed in a manner that prevents the accumulation of water within the wall assembly by providing a water-resistant barrier behind the exterior cladding and a means of draining to the exterior water that penetrates the exterior cladding. R703.1.1
3. Post the attached Inspection Record Card on the jobsite.
MSBC1300.0210 subp 3
4. Every permit issued shall become invalid unless the work authorized by the permit is commenced within 180 days after its issuance, or if the work authorized by the permit is suspended or abandoned for a period of 180 days after the time the work is commenced. MSBC1300.0120 subp 11
5. This structure must comply with all portions of the Minnesota State Building Code whether noted on this plan or omitted. Failure to note any detail(s) on the plan does not remove the builder from the responsibility of complying with the Building Code. Plan review was done in accordance with the current Minnesota Building Code. Plan review does not waive any additional code compliance issues found on site. MSBC1300